

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10361-0000

API NUMBER Drilled 4-56

LEASE NAME Heintz

WELL NUMBER 1-31

1315' Ft. from S Section Line

1301' Ft. from ~~XX~~ Section Line

SEC. 31 TWP. 34 SRGE. 42 ~~(XX)~~ or (W)

COUNTY Morton

Date Well Completed 4-56

Plugging Commenced 3-10-99

Plugging Completed 3-11-99

RECEIVED
KANSAS CORPORATION COMMISSION

4-9-99

NOTICE: Fill out completely
APR 09 1999 and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Coastal Oil & Gas Corp.

ADDRESS 9 Greenway #2751 - Houston, TX 77046

PHONE#(713 877-7590) OPERATORS LICENSE NO. 6594

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-10-99 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? No - old file - limited information

Producing Formation Wabaunsee Depth to Top 2648 Bottom 2663 T.D. 3160

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>605</u>	<u>-</u>
				<u>5 1/2</u>	<u>3070</u>	<u>727</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Schlumberger set CIBP + 2 sx cmt from 2600 to 2580. Shot & pulled 5 1/2 to 630. Circ. hole w/mud. Mixed 50 sx plug 630 to 480. Mixed 10 sx plug 40 to 0. Cut off & capped 8 5/8 4 ft. below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coastal Oil & Gas

STATE OF Texas COUNTY OF Harris, ss.

Deborah Moore


(Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Deborah Moore

9 Greenway #2751

(Address) Houston TX 77046



SWORN TO before me this 7th day of April, 19 99.

Lizzie Lucille Canik
Notary Public

My Commission Expires: 9-14-99