

10-14-86

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20,823-0000

LEASE NAME CENTRAL LIFE "A"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 34 TWP. 34S RGE. 42 (X) or (W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 9/10/86

Character of Well D&A

Plugging Commenced 9/10/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/10/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1320	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugs spotted thru DP; 50 sxs 4700-4470', 50 sxs 2500-2270', 50 sxs 1350-1120', 40 sxs 600-420'. A wooden wiper plug pushed to 40' w/10 sxs 40' to 0' and 15 sxs circ in rathole. Cement type: 60/40 Pozmix w/6% gel. Heavy drilling mud spotted between each plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address P. O. Box 1589, Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Engineer (Employee of Operator) or ~~NOTARY PUBLIC~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) P. O. Box 351, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 86



Beverly J. Williams
Notary Public

My Commission Expires November 21, 1986

OCT 14 1986