

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-00030-0000

API NUMBER _____

LEASE NAME FEDERAL LAND BANK

WELL NUMBER 1

SPOT LOCATION C NW

SEC. 34 TWP. 34S RGE. 42 (E) or (W) (W)

COUNTY Morton

Date Well Completed 11/9/55

Plugging Commenced 3/25/85

Plugging Completed 3/27/85

4-10-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pan Eastern Exploration Company

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5598

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City

Is ACO-1 filed? No If not, is well log attached? yes

Producing formation Cherokee Depth to top 4482 bottom 4514 T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	Gas	4482	4514	8-5/8"	1518	-0-
				5-1/2	4597	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. The well was plugged by spotting 50 sacks cement from 4250' to 4513', 50 sacks cement from 1350' to 1600' and 15 sacks from 3' to 70'. The casing was cut off 3' below the surface and capped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547
Address 620 S. Lincoln, Liberal, Kansas 67901

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEWARD, ss.

APR 10 1985

Paul Campbell (employee of operator) or
Operator of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Campbell
(Address) P. O. Box 351, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1985

BEVERLY J. WILLIAMS
Seward County, Kansas
My Comm. expires: November 21, 1986

Beverly J. Williams
Notary Public

WELL LOG

COMPANY PANHANDLE EASTERN PIPE LINE COMPANY
FARM Federal Land Bank **NO.** 134
TOTAL DEPTH 4600'
COMM. October 4, 1955 **COMP.** October 25, 1955
CONTRACTOR GARVEY DRILLING COMPANY

SEC. 34 T. 34S. 42W
LOC. C NW
COUNTY Morton

CASING 8-5/8" @ 1506' w/700 sacks
 5-1/2" @ 4588' w/200 sacks

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

70	Sand & Clay	2605	Shale & Lime
140	Sand & Shale	2772	Lime, Shale & Red Rock
485	Red Bed Shale	2920	Lime & Shale
770	Sand Red Rock, Shells	3425	Lime
795	Gypsum	3612	Lime & Shale
845	Red Bed	3771	Lime
890	Gypsum	3866	Lime & Sandy Shale
1055	Shells	3879	Lime
1200	Red Rock, Red Bed Sand	3922	Lime & Shale
1270	Red Rock & Shells	3985	Lime
1342	Red Bed	4015	Lime & Shale
1360	Anhydrite	4100	Lime
1386	Shale & Shells	4131	Lime & Shale
1404	Anhydrite	4224	Shale
1412	Shale	4285	Shale & Sand
1440	Anhydrite	4335	Shale
1480	Shale, Shells, Red Rock	4345	Shale & Sand
1523	Gypsum & Anhydrite	4363	Sand
2065	Shale, Red Rock & Gypsum	4405	Shale & Lime
2137	Anhydrite & Red Rock	4473	Shale & Sand
2325	Red Rock & Shale	4541	Sand
2450	Shale, Shells & Red Rock	4556	Sand & Lime
2515	Lime	4600	Lime
		4600	T.D.

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1985

CONSERVATION DIVISION
Wichita, Kansas



State of KANSAS
 County of SEDGWICK

I, Robert E. Campbell of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the Federal Land Bank Unit 134 well

Subscribed and sworn to before me this 7th day of November 19 55

My Commission Expires: August 8, 1959


Robert E. Campbell

Gloria Morrison
 NOTARY PUBLIC