

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-129-20934-00-00

RECEIVED

7-9-03

LEASE NAME Austin B

JUL 09 2003

TYPE OR PRINT

WELL NUMBER 1

KCC WICHITA

NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

3300 Ft. from S Section Line

580 Ft. from E Section Line

LEASE OPERATOR Oxy USA, Inc.

SEC. 6 TWP. 34 RGE. 42 (E) or (W)

ADDRESS 1701 N. Kansas PO Box 2528 Liberal KS 67905 COUNTY Morton

PHONE(S) (620) 629 4200 OPERATORS LICENSE NO. 5447

Date Well Completed 2-15-89

Character of Well D+A

Plugging Commenced 6-3-03

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-4-03

The plugging proposal was approved on 6-2-03 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Marmaton Depth to Top 3506 Bottom 3516 T.D. 4775

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1264	—
				5 1/2	4774	—

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each so
CIBP @ 3350 Load hole w/mud to 1300, mixed 25 sx plug from 1300 to 1100, mud to 500, mixed 57 sx plug from 500 to 0 + pres. up to 500
Mixed 15 sx down annulus from 60 to 0 + pres. up to 500. Cut off 8 5/8 + 5 1/2 + capped 8 5/8 3 ft. below GIL.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 2003



Kath R. Poulton
Notary Public

My Commission Expires: November 8, 2006



OXY USA Inc.
1701 N. Kansas, Liberal, KS 67901
P.O. Box 2528, Liberal, KS 67905-2528

RECEIVED
JUL 09 2003
KCC WICHITA

July 03, 2003

Kansas Corporation Commission
Wichita State Office Bldg.
130 South Market, Room 2078
Wichita, Kansas 67202

Re: Well Plugging Record (CP-4)
OXY USA INC.
AUSTIN B # 1
API # 15-129-20934
Section 6-34S-42W Morton County; Ks.

To Whom It May Concern:

Please find enclosed the Well Plugging Record (CP-4) for the subject well. A workover pit was applied for but not needed, therefore, find the approved pit application signed and dated. Thanks for your help.

If there are any questions or you require further information, please contact me at the above address or by Phone at (620) 629 - 4232.

Sincerely,

A handwritten signature in black ink, appearing to read "Kenny L. Andrews".

Kenny L. Andrews
Engineering Technician
Liberal, Kansas