

API NUMBER 15-129-20010-0000

LEASE NAME Government

WELL NUMBER #1-9

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 9 TWP. 34 RGE. 42 (E) or (W)

COUNTY Morton

Date Well Completed 9-28-67

Plugging Commenced 11-12-86

Plugging Completed 11-15-86

12-17-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS 211 N. Robinson, Suite 1700, Okla. City, Okla.
 73102

PHONE# (405) 239-7031 OPERATORS LICENSE NO. 6593

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4280 Bottom 4282 T.D. 4990

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Gas	4280	4282	8-5/8	1270	0'
				4-1/2	4990	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
CIBP at 4195', 6 sxs 60:40 POZ 4195' to 4091', 9. ppg mud 4091' to 1320'. Shot 4 holes at 1320' pump 325 sxs 60:40 POZ displaced to 800' w/9 ppg mud. Shot 4 holes at 350'. Circulated cmt. to surface w/137 sxs Lite, displ. to 3'. Cutoff casing 3' below GL, weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell-Schlumberger License No. _____

Address Liberal, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

C. Brad Crouch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Brad Crouch

(Address) 211 N. Robinson, Suite 1700, Okla. City
 Oklahoma 73102

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1986

Diana Thompson
 My Commission Expires: November 18, 1988 Notary Public, State Corporation Commission