

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


9-21-76

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
245 North Water
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines. Morton County. Sec. 15 Twp. 34 Rge. (E) 42 (W)

Lease Owner Pan Eastern Exploration Company

Lease Name Riley "B" Well No. 1-15

Office Address P. O. Box 828 Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed May 28 1975

Application for plugging filed August 24 1976

Application for plugging approved August 25 1976

Plugging commenced September 8 1976

Plugging completed September 10 1976

Reason for abandonment of well or producing formation Mechanical problems - replaced well

If a producing well is abandoned, date of last production August 18 1976

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Topeka Depth to top 2893 Bottom 3071 Total Depth of Well 3231 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Ogallala	Fresh Water	100	350	7"	3200	915
Topeka	Gas	2893	3071	10-3/4"	600	None
Note: Also see attached well log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 3 sxs hulls and 50 sxs cement down well followed by a rubber plug. Plug stopped at 2600' and held.

Shot 7" casing at 2036', 1210', 1026', and loose at 915'. Spotted 25 sxs from 800 to 900 feet.

Pulled casing to 500' and spotted 50 sxs cement. Pulled remaining casing. Checked and found cement plug at 450'.

Placed 20 sxs cement from 30-3'. Cut casing off and capped same 5' below ground level.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service

Address P. O. Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

Jack P. Phillippe (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

P. O. Box 828, Liberal, Kansas 67901

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September, 1976

My commission expires January 20, 1980

Virginia Newhouse
Notary Public.



WELL LOG

COMPANY PANHANDLE EASTERN PIPELINE COMPANY

SEC. 15 T. 34S R. 42W

FARM Riley

NO. 1-15

LOC. SE/4


TOTAL DEPTH 3231

COUNTY Morton

COMM. 4-23-55

COMP. 5-19-55

CONTRACTOR GARVEY DRILLING COMPANY



CASING 10-3/4" @ 600 (275 sx)
7" @ 3200 (250 sx)

ELEVATION unknown

PRODUCTION unknown

FIGURES INDICATE BOTTOM OF FORMATIONS

100	Surface Sand
200	Coarse Sand
650	Red Bed & Sand, Gypsum
910	Red Bed, Sand, Anhydrite
1090	Sand Red Bed
1335	Red Bed - Sand - Anhydrite
1545	Red Bed Sand Shale
1725	Red Bed & Shale
2092	Red Bed & Anhydrite streaked Shale
2276	Red Bed & Shale & Lime
2415	Shale & Lime
2473	Lime & Shale
2646	Shale & Lime
3015	Lime & Shale
3231	Lime
3231	R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1976
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS

County of SEDGWICK

ss:

I, Robert F. White of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1-15 Riley well

Robert F. White
Robert F. White

Subscribed and sworn to before me this 2nd day of June 19 55

My Commission Expires: 11 August 1958

John McKeon
NOTARY PUBLIC