

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 6/21/55 Spud Date

LEASE NAME Scott

WELL NUMBER 1-18

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 18 TWP. 34S RGE. 42 (E) or (W)

COUNTY Morton

Date Well Completed 6/30/55

Plugging Commenced 9/29/94

Plugging Completed 9/29/94

10-19-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/29/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Drillers Log

Is ACO-1 filed? Filed If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.O. 3096

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	498'	3'
				5 1/2	3090'	833'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Pmp 1 sk hulls & 25 sxs cmt plg from 2569-2369'. Displace w/mud. Shot 5 1/2" csg @ 833'. Spot 25 sxs cmt plg from 800-700'. TOH w/csg to 530'. Spot 50 sxs cmt plg from 530-380'. TOH & spot 10 sxs cmt plg from 34-4'. Cut off 8 5/8" csg 3' below ground level and cap. KCC Witness - Glenn Barlow. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731 Phone: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes

Leslie I. Barnes

(Address) P. O. Box 351, Liberal, KS 67905-0351

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 19 1994

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 94

Cheryl Steers

Notary Public

CONSERVATION DIVISION
WICHITA, KS Commission Expires:

