

5-5-75

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Morton County, Sec. 18 Twp. 34S Rge. 42 (E) (W) X
Location as "NE/CNW/SE" or footage from lines: G SW SW
Lease Owner: Davis Drlg., Inc.
Lease Name: Scott Well No. 1-18
Office Address: P. O. Box 757, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole): Gas
Date well completed: 19
Application for plugging filed: April 21 1975
Application for plugging approved: April 22 1975
Plugging commenced: 4-22 19 75
Plugging completed: 4-24 19 75
Reason for abandonment of well or producing formation: Depleted, No production.

If a producing well is abandoned, date of last production: August 1974
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Clarence Thomas
Producing formation: Depth to top: Bottom: Total Depth of Well: 3399
Show depth and thickness of all water, oil and gas formations: T.D. 5510

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1173	none
				1 1/2	3399	2230

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 1 sk. of hulls & 10 sks. of cement from 3312 to 3200
Pump 50 sks. of cement from 1200 to 1100
Pump 35 sks. of cement from 600 to 500
Put 10 sks. of cement from 33 to 3

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1975
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor: Sargents Casing Pulling Service Kansas No. 511
Address: Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Barton ss.
H. C. Davis, President, Davis Drlg. Inc. (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. C. Davis
P.O. Box 757, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 2nd day of May, 1975

My commission expires Oct. 5, 1978

Marilyn Rodgers, Notary Public.



DRILLERS LOG

Scott #1-18
 Location: 660' NSL & 660' EWL
 Section: 18-34S-42W
 Morton County, Kansas
 Company: Davis Drlg., Inc., etal
 Caroline W. Law
 Contractor: Davis Drlg., Inc.

Comm: 12-22-65
 Comp: 1-14-66
 Rotary Total Depth: 5510'
 Casing: 8-5/8" at 1173'
 4-1/2" at 3399'

0	158	Sand & Clay
158	330	Surface Sand & Red Bed
330	454	Surface Sand & Shale
454	749	Shale & Anhydrite
749	1060	Shale & Shells W/ Gyp Streaks
1060	1175	Shale & Anhydrite
1175	1715	Shale
1715	1940	Shale & Gyp
1940	2155	Shale & Shells
2155	2450	Shale
2450	2575	Lime & Shale
2575	2960	Shale & Lime
2960	3065	Lime & Shale
3065	3140	Shale & Lime
3140	3965	Lime & Shale
3965	4120	Sandy Lime & Shale
4120	4198	Lime & Shale
4198	4475	Shale & Lime
4475	4540	Shale, Lime & Sand
4540	4602	Lime, Shale & Keys Sand
4602	4638	Shale & Lime
4638	4648	Sand
4648	4668	Sand & Shale
4668	4697	Sand
4697	4796	Shale & Sand
4796	4903	Sandy Lime
4903	5008	Sandy Lime w/ Chert
5008	5010	Sandy Lime
5010		Total Rotary Depth

Cemented 8-5/8" casing
 at 1173' with 500 sacks
 Posmix, 3% Gel, 100 sacks
 Common & 2% Calcium Chloride.

RECEIVED
 STATE CORPORATION COMMISSION

APR 22 1966

CONSERVATION DIVISION
 Wichita, Kansas


Lost Circulation @ 4952'
 Cemented 4-1/2" casing at
 3399' with 150 sacks common,
 4% Gel, 18% salt, 12-1/2#
 Gilsonite per sack.

I certify that this is the true and correct copy of the above log to the best of my knowledge.


 Kenneth G. Fischer, Sec.

Subscribed and sworn to before me this 18th day of January, 1966.

My Commission Expires: October 4, 1969


 Katherine L. Morrow
 Notary Public