

9-19-03

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 129-21709-00-00
LEASE NAME Ralston
WELL NUMBER 2-19
1620 Ft. from S Section Line
4048 Ft. from E Section Line
SEC. 19 TWP. 34 SRGE. 42 (E) or (W)
COUNTY Morton
Date Well Completed 9-9-03
Plugging Commenced 9-8-03
Plugging Completed 9-9-03

RECEIVED

SEP 19 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman, L.L.C.

ADDRESS 3200 First Place Tower, Tulsa, OK 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 32638

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-8-03 (date)

by Scott (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Dry Depth to Top _____ Bottom _____ T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1393	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Hole full of 9.0 ppg mud. Spotted 100 sks 65/35 light cement w/6% gel @ 3400'. Spot 50 sks 65/35 light cement w/6% gel.
Discovered that 20 its drill pipe had fallen off of drill stem. POOH. TIH. Tagged cement @ 700'. Washed & drilled to 1528. TOOH.
Spot 50 sks 65/35 light cement @ 1423. Spot 50 sks 65/35 light cement w/6% gel @ 500'. Spot 10 sks 65/35 light cement w/6% gel @ 40'.
Job complete @ 7:45 a.m. 9-9-03

Name of Plugging Contractor Schlumberger License No. N/A

Address Perryton, TX

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C.

STATE OF Oklahoma COUNTY OF Tulsa, ss.


James Piland, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 15 E. 5th, Suite 3200, Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 2003

[Signature]
Notary Public
9/10/04 # 8057



Form 05-1
Revised 05-88