

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-21048-0000

LEASE NAME FEDERAL A.

WELL NUMBER 1-22

2310 FSL Ft. from S Section Line

2310 FEL Ft. from E Section Line

SEC. 22 TWP. 34S RGE. 42 (E) or (W)

COUNTY Morton

Date Well Completed 1/25/91

Plugging Commenced 5/27/97

Plugging Completed 5/28/97

9-8-97

RECEIVED  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.  
1997 SEP 8 P 12:14

LEASE OPERATOR OXY USA INC.

ADDRESS P.O. BOX 300

PHONE# (918) 561-3548 OPERATORS LICENSE NO. 5447

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 10, 1997 (date)

by Mr. DAVID WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? Yes

Producing Formation D&A Depth to Top -- Bottom -- T.D. 4952'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MORROW	(DRY)	--	--	8 5/8"	1514'	
				5 1/2"	4952	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set  
PLEASE REFER TO THE ATTACHED

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. GIBSON License No. \_\_\_\_\_

Address LIBERAL, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

RAYMOND HUI

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Raymond Hui

(Address) P.O. BOX 300, TULSA, OK 74102-0300

SUBSCRIBED AND SWORN TO before me this 6th day of JUNE, 19 97

Elizabeth K. Jensen  
Notary Public

My Commission Expires: 2-26-2000

Federal A1-22:

5-1/2 @ 4952 PBD @ 4912' PERFS: 4409-12'

May 23, 1997

MIRUDDWOU. SICP 100 PSIG BLEW CSG DOWN 10 MINS. POH WITH 2-3/8" TBG. RU HES SET CIBP @ 4380' RD HES. RIH WITH 140 JTS TBG TAGGED CIBP @ 4380' RU PUMP TRUCK CIRCULATED CSG WITH 9# DRILLING MUD. SIDS FOR HOLIDAY WEEKEND. NO REPORT UNTIL WED 5-28-97. HES \$1567 JW GIBSON \$1007

FEDERAL A1-22:

May 27, 1997

RU HES CEMENTER SPOTTED 8 SX PLUG FROM 4380 TO 4318 (TOP OF CIBP). POH WITH 43 JTS TBG SPOTTED 15 SX PLUG FROM 3035' TO 2920' (DV TOOL @ 2980'). POH WITH 45 JTS TBG SPOTTED 45 SX PLUG FROM 1620' TO 1272' ( SURFACE PIPE @ 1514'). POH WITH 27 JTS TBG SPOTTED 35 SX PLUG FROM 550' TO 300' ( FRESH WATER PLUG). POH WITH REMAINDER OF TBG. HOOKED UP TO ANNULUS UNABLE TO PUMP. PICKED UP ON 5-1/2 REMOVED SLIPS. RAN 1" PIPE IN ANNULUS TO 40' PUMPED CEMENT TO SURFACE. POH WITH 1" PIPE. RAN 1" PIPE IN 5-1/2" TO 70' SPOTTED 10 SX PLUG FROM 70' TO SURFACE. LD 1" PIPE RD HES PUMP TRUCK. ALL CEMENT PLUGS WERE CLASS H CEMENT MIXED AT 16.4 PPG. ALL DISPLACEMENT FLUID WAS 9# DRILLING MUD. SDFN. JW GIBSON \$1382 HES \$5742

FEDERAL A1-22:

May 28, 1997

RDMODDWOU. CUT OFF AND CAPPED CSG. WELL P&A'D 5-28-97. JW GIBSON \$293 CHRIS HUNT \$664 J&J \$644