

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20744-0000

LEASE NAME Bradshaw C

WELL NUMBER 3

SPOT LOCATION C S/2 NW SW

SEC. 23 TWP. 34 RGE. 42 ~~WWW~~ (W)

COUNTY Morton

Date Well Completed 2-14-85

Plugging Commenced 2-13-85

Plugging Completed 2-14-85

3-18-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 N.W. 58th Street, Okla. City, Okla. 73112

PHONE # (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 2

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation --- Depth to top --- bottom --- T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1378'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 75 sx cmt. plug 4950-4800' Keyes, 50 sx 4750-4650' Morrow, 100 sx 3150-2920' Topeka, 50 sx 1428-1328' (50' in & out of surf. csg.) 50 sx 690-590' water sands, 10 sx 40'-4' surface. Filled rat and mouse holes w/10 sx each.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Zenith Drilling Corp.
Address 505 Fourth Financial Center
Wichita, KS 67202

STATE CORPORATION COMMISSION 5141

MAR 18 1985

STATE OF Oklahoma COUNTY OF Oklahoma

CONSERVATION DIVISION
Wichita, Kansas

D.G. Oliver (employee of operator) ~~WWW~~

~~WWW~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D.G. Oliver

(Address) 3545 N.W. 58th Street
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 85

Joyce L. Darter
Notary Public

My Commission expires: 6-12-88