

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
201 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-129-10548-0000

API NUMBER 1-15-59

LEASE NAME Taloga Morrow "G"

WELL NUMBER 202

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 26 TWP. 34S RGE. 42 XEX or (W)

COUNTY Morton

Date Well Completed 1-15-59

Plugging Commenced 9-16-91

Plugging Completed 9-18-91

10-16-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-15-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow "G" Depth to Top 4542 Bottom 4576 T.D. 4700

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS AND WATER RECORDS COMMISSION | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
OCT	6 1991					
				8 5/8	1418	0
				5 1/2	4699	2408
CONSERVATION DIVISION WICHITA, KS						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set TIH w/1-1/4" tbg to 4500'. LD hole w/9 ppg DM, pmpd 1 sx hull & 25 sxs cmt from 4500'-4300'. TOH w/1-1/4" tbg to 4300'. TOH w/1-1/4" tbg. Shot 5-1/2" csg off @ 2408 (freepoint). Pmpd 30 sxs cmt from 2400'-2300'. pmpd 40 sxs cmt from 1460'-1360', pmpd 30 sxs cmt from 650'-550', pmpd 10 sxs cmt from 40'-3'. Rec 65 its 5-1/2" csg. Cut off & capped 8-5/8" csg 3' below GL. KCC Rep -  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547  
Restore location.

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams  
Beverly J. Williams, Eng. Tech.  
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 91

Cheryl Steers  
Notary Public

My Commission Expires: \_\_\_\_\_

