

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-20777-00-00  
Spot: W2NENWNE Sec/Twnshp/Rge: 25-11S-26W  
330 feet from N Section Line, 1880 feet from E Section Line  
Lease Name: JAMISON 'A' Well #: 1  
County: GOVE Total Vertical Depth: 4695 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4214		175 SX
SURF	8.625	348		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2015 10:00 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: TODD L. DINKEL Company: G L M COMPANY Phone: (785) 639-5415

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perforations: 4048' - 4052'.  
Shot perforations at 2155', 1273' and 340'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/08/2015 6:00 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 3998' and pumped 80 sx cement w/200 # hulls. Pulled tubing to 2996' and pumped 105 sx cement w/100 # hulls. Pulled tubing to 1508' and pumped 150 sx cement. Pulled tubing out. Topped off with 90 sx cement. Tied on to backside and squeezed with 75 sx cement.  
  
GPS: 39.07351 -100.15508

**Perfs:**

Top	Bot	Thru	Comments
4048	4052		

Remarks: GLOBAL CEMENT TICKET # 1676

Plugged through: TBG

**MAY 27 2015** *CKM*

District: 04

Signed *Marvin Mills*  
(TECHNICIAN) *CM*

MAY 12 2015