

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-115-21486-00-00  
Spot: S2SENESE Sec/Twnshp/Rge: 33-18S-2E  
1540 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SCULLY Well #: 1  
County: MARION Total Vertical Depth: 2938 feet

Operator License No.: 31389  
Op Name: NOBLE PETROLEUM, INC.  
Address: 8918 W. 21ST ST. N. SUITE 200 #304  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		140 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2014 12:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: C&G DRILLING, INC. Phone: (620) 583-4306

Proposed Plugging Method: ARB 35 SXS. 35 SXS 50' BELOW BOTTOM SURFACE. 60' - 25 SXS. 30 SXS IN THE RAT HOLE AND 20 MOUSE HOLE.

Plugging Proposal Received By: B. J. HOPE WitnessType: NONE  
Date/Time Plugging Completed: 10/05/2014 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

HOLE FILLED WITH DRILLING MUD FROM RTD 2938' TO 275'. SPOTTED 35 SX PLUG FROM 275' TO 150'. SPOTTED DRILLING MUD TO 60'. CEMENTED TO SURFACE WITH 60 SX. PUMPED 20 SX IN MOUSEHOLE AND 30 SX IN RATHOLE. ALL CEMENT 6040 POZ + 4% GEL.

Remarks:  
Plugged through: DP

MAY 27 2015 *ckm*

District: 02

Signed Jeff Klock DISTRICT SUPERVISOR  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 14 2015

CONSERVATION DIVISION  
WICHITA, KS