

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24394-00-00
Spot: NENWNW Sec/Twnshp/Rge: 28-19S-24W
4894 feet from S Section Line, 4305 feet from E Section Line
Lease Name: FANSHIER HD Well #: 1-28
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1650		WITH 190 SX CMT
PROD	4.5	4395	0	WITH 200 SX CMT
SURF	8.625	208		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2015 12:30 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 20 SX CMT & 200# HULLS. PULL TBG TO 1380' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2015 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4200' & PUMP 36 BBL GEL WATER, 30 SX CMT & 200# HULLS. RUN TBG TO 1380' & PUMPED 110 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4249	4253		
4248	4252		

Received
KANSAS CORPORATION COMMISSION
MAY 22 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

MAY 27 2015 *CKM*

District: 01

Signed

Michael J. Maier

(TECHNICIAN)

RECEIVED
MAY 19 2015
KCC DODGE CITY

MP

MA