

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24290-00-00
Spot: SENESWNW Sec/Twnshp/Rge: 24-8S-17W
1860 feet from N Section Line, 1025 feet from W Section Line
Lease Name: CHESNEY Well #: 1
County: ROOKS Total Vertical Depth: 3500 feet

Operator License No.: 6677
Op Name: SANDLIN OIL CORPORATION
Address: 621 17TH ST STE 2055
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3496	1900	150 sx
SURF	8.625	215		160 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2015 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRED BARBER Company: SANDLIN OIL CORP Phone: (785) 623-1517

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/200 # hulls.
Perforations: 3444' - 3446'. CIBP at 3430'.
Perforations: 3286' - 3290', 3256' - 3260', 3241' - 3247', 3219' - 3223' and 3018' - 3084'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2015 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

05/12/2015- Express ran in hole with tubing to 3428'. Quality rigged to tubing and pumped 50 sx cement w/200 # hulls mixed in.
05/13/2015- 9:00am. G & J Cased Hole Solutions ran 3 point shot pipe at 1900'. Pulled to 1250', mixed and pumped 50 sx cement. Pulled casing to 770' and pumped 100 sx cement. Pulled casing to 265' and pumped 50 sx cement. Pulled casing to 42' and pumped 10 sx cement. Hole standing full.

GPS: 39.34546 -099.17236
SE NE SW NW
3404' FSL 4292' FEL

Remarks: QUALITY OILWELL CEMENTING TICKET # 1413 HOLE PLUGGED THROUGH TUBING AND CASING

Plugged through: TBG

MAY 27 2015 *CFM*

District: 04

Signed *[Signature]*
(TECHNICIAN)

CM