

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21582-00-00
Spot: SENWSWSE Sec/Twnshp/Rge: 8-31S-19W
676 feet from S Section Line, 2065 feet from E Section Line
Lease Name: LOHRDING Well #: 8-1
County: COMANCHE Total Vertical Depth: 5828 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5169		WITH 10 SX CMT
CIBP		5172		
CIBP		5280		
COND	13.375	374		WITH 360 SX CMT
PROD	5.5	5826	1596	WITH 215 SX CMT
SURF	8.625	946		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2015 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5069' WITH 10 SX CMT. PLUG AT 1160' WITH 100 SX CMT. PLUG AT 420' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 04/13/2015 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5169' WITH 10 SX CMT. 1ST PLUG AT 1170' WITH 100 SX CMT. 2ND PLUG AT 424' WITH 120 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5414	5446		
5181	5494		
5119	5141		
5060	5065		
5030	5045		

Received
KANSAS CORPORATION COMMISSION
MAY 20 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

MAY 27 2015 *ckm*

District: 01

RECEIVED
MAY 14 2015
KCC DODGE CITY

Signed *Eric MacLaren*
(TECHNICIAN)