

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21794-00-00
Spot: N2NWSESE Sec/Twnshp/Rge: 25-33S-7W
1040 feet from S Section Line, 990 feet from E Section Line
Lease Name: JESSICA Well #: 1-25
County: HARPER Total Vertical Depth: 5161 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5050		
PROD	5.5	5161	1466	130 SX
SURF	8.625	341		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2015 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: MICHAEL HULL Company: SANDRIDGE EXPL Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2015 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CIBP SET AT 4890' & CAPPED WITH 6 SXS CEMENT. LOADED HOLE WITH MUD. SHOT CASING AT 2472', 2014' & LOOSE AT 1466'. LAYED DOWN CASING & RAN TUBING TO 1164', SPOTTED 35 SXS CEMENT. PULLED TUBING TO 756' SPOTTED 35 SXS CEMENT. PULLED TUBING TO 405' & CIRCUALTED CEMENT TO SURFACE WITH 125 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
5104	5108	CSG	
4941	4943	CSG	

Remarks: ORR ENTERPRISES - CLASS "C"

Plugged through: TBG

MAY 27 2015
CKM

District: 02

Signed _____
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 14 2015
CONSERVATION DIVISION
WICHITA, KS