

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21730-00-00  
Spot: SWNWNSW Sec/Twnshp/Rge: 6-27S-19W  
2129 feet from S Section Line, 1395 feet from W Section Line  
Lease Name: ROSE Well #: 1-6  
County: KIOWA Total Vertical Depth: 4922 feet

Operator License No.: 33036  
Op Name: STRATA EXPLORATION, INC.  
Address: PO BOX 401  
FAIRFIELD, IL 62837

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
CIBP		4228		
CIBP		4820		
PROD	5.5	4928	1929	WITH 250 SX CMT
SURF	8.625	519		WITH 350 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2015 12:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: MICHAEL POLLY Company: STRATA EXPLORATION Phone: (719) 342-5600

Proposed Plugging Method: SET CIBP @ 4150' WITH 2 SX CMT. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/13/2015 8:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4150' WITH 2 SX CMT. 1ST PLUG AT 1317' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 559' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. CMT CIRCULATED BUT WAS FALLING BACK. 5/13/15: TOPPED OFF WITH 40 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4232	4242		
4201	4209		

Received  
KANSAS CORPORATION COMMISSION  
MAY 20 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

MAY 27 2015  
cm

District: 01

Signed



(TECHNICIAN)

RECEIVED  
MAY 13 2015  
KCC DODGE CITY

JA