

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24395-00-00
Spot: NENWSW Sec/Twnshp/Rge: 17-32S-6E
2296 feet from S Section Line, 4152 feet from E Section Line
Lease Name: ROGERS Well #: 1 NIETAS
County: COWLEY Total Vertical Depth: 3422 feet

Operator License No.: 5437
Op Name: TOMCO OIL, INC.
Address: 22150 SE COLE CREEK RD
ATLANTA, KS 67008

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3200		
PROD	5.5	3424	1510	100 SX
SURF	8.625	328		180 SX
T1	2.375	3420		

Well Type: OIL UIC Docket No: . Date/Time to Plug: 04/08/2015 8:00 AM
Plug Co. License No.: 34900 Plug Co. Name: KING'S WELL SERVICE LLC
Proposal Rcvd. from: TOM BLAIR Company: TOMCO OIL Phone: (620) 394-2324

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/08/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3050', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1510', LAYED DOWN 36 JOINTS OF 5 1/2" CASING, (1,510'). RIH W/TBG @ 380', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/CEMENT. ELITE CEMENT TICKET #2240.

Perfs:

Top	Bot	Thru	Comments
3100	3250	CSG	

Remarks:

Plugged through: TBG

MAY 27 2015
ckm

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 14 2015

CONSERVATION DIVISION
WICHITA, KS

JK