

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24432-00-00
Spot: SESWSWNW Sec/Twnshp/Rge: 17-32S-6E
2611 feet from N Section Line, 533 feet from W Section Line
Lease Name: ROGERS Well #: #2 NIETAS
County: COWLEY Total Vertical Depth: 3558 feet

Operator License No.: 5437
Op Name: TOMCO OIL, INC.
Address: 22150 SE COLE CREEK RD
ATLANTA, KS 67008

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3385		PACKER TYPE AND SETTING DEPTH: ARROW LOK SET @ 3385
PROD	5.5	3433	1520	175 SX
SURF	8.625	315		165 SX
T1	2.375	3385		
T1	2.375	3400		

Well Type: SWD UIC Docket No: D30921.0 Date/Time to Plug: 04/09/2015 8:00 AM
Plug Co. License No.: 34900 Plug Co. Name: KING'S WELL SERVICE LLC
Proposal Rcvd. from: TOM BLAIR Company: TOMCO OIL Phone: (620) 394-2324

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/10/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3400', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1520', LAYED DOWN 36 JOINTS OF 5 1/2" CASING, (1,520'). RIH W/ TBG @ 370', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/ CEMENT. ELITE CEMENT TICKET #2070.

Perfs:

Top	Bot	Thru	Comments
3433	3558	OH	

Received
KANSAS CORPORATION COMMISSION
MAY 14 2015

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

MAY 27 2015
ckm

cc:UIC