

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24476-00-01
Spot: NWSENW Sec/Twnshp/Rge: 17-32S-6E
3322 feet from S Section Line, 3300 feet from E Section Line
Lease Name: ROGERS Well #: 3 NIETAS
County: COWLEY Total Vertical Depth: 3471 feet

Operator License No.: 5437
Op Name: TOMCO OIL, INC.
Address: 22150 SE COLE CREEK RD
ATLANTA, KS 67008

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3471	1515	100 SX
SURF	8.625	306		165 SX
T1	2.875	3150		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2015 8:00 AM
Plug Co. License No.: 34900 Plug Co. Name: KING'S WELL SERVICE LLC
Proposal Rcvd. from: TOM BLAIR Company: TOMCO OIL Phone: (620) 394-2324

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/07/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3000', DUMP BAILED 2 SXS CEMENTON TOP OF PLUG. CUT CASING @ 1515', LAYED DOWN 36 JOINTS OF 5 1/2" CASING, (1,515'). RIH W/ TBG @ 370', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/ CEMENT. ELITE CEMENT TICKET #2238.

Perfs:

Top	Bot	Thru	Comments
3050	3090	CSG	

Remarks:

Plugged through: TBG

MAY 27 2015
clm

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 14 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

JK