

1040985 7-26

API NUMBER 15- 151-21,373-0001

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

SE SE SW, SEC. 30, T 28 S, R 12 W  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303

Lease Name Skiles Well # 1

Operator: Canaday Oil Corporation

County Pratt 155.25

Name: 842 Toh-N-Hah Trail

Well Total Depth 4777 feet

Address: Wichita, KS 67212-4538

Conductor Pipe: Size 13 3/8 feet 317

Surface Casing: Size 8 5/8 feet 1017

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:15 p.m. Day: 26 Month: 7 Year: 19 95

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Peris at  
were: 4 1/2" at 4777' w/250 sx cement, PBT 4730', 4472-82, 4323-29, 4211-15, 3926.5, 3930.5'  
1st plug sand back to 3875' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2 p.m. Day: 26 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3875' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 625 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3150' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I ( ) observe this plugging.

DATE AUG 03 1995

Signed *Stephan J. Pfeiffer* (TECHNICIAN)

INV. NO. 43233  
7-26