

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,373-00-00

SESE SW Sec. 30, T 28 S, R 12 W/8

330 feet from ~~W~~/S section line

2310 feet from W/8 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8194

Lease Name Shiles Well # 24-4-30

Operator: Energetics Inc.  
Name &  
Address 116 Inverness Drive East,  
Englewood Colo. 80112

County Pratt

Well Total Depth 4788 feet

Conductor Pipe: Size \_\_\_\_\_ feet 155.61

Surface Casing: Size 8 5/8 feet 1016

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Springs Drilling Inc. License Number 5381

Address Box 4287 Hunger Station, Wichita, Kansas 67208

Company to plug at: Hour: 6:30 AM, Day: 15 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Jenny Austin

(company name) Big Springs Drilling Inc. (phone) \_\_\_\_\_

were: 1st plug @ 4700' w/ 50 sbp cement.

2nd plug @ 1060' w/ 50 sbp cement.

3rd plug @ 620' w/ 40 sbp cement.

4th plug @ 40' to 0' on solid bridge w/ 10 sbp cement.

Circulate 15 sbp cement in rat hole. Halliburton cemented w/

60/40 zogg w/ 2% gell.

Signed Paul A. Luthis  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:00 AM, Day: 16 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT

1st plug. filled hole full of heavy mud & spotted 50 sbp cement.  
through drill pipe @ 4700'. 2nd plug w/ hole full of heavy mud spotted 50 sbp  
cement through drill pipe @ 1060'. 3rd plug w/ hole full of heavy mud  
spotted 40 sbp cement through drill pipe @ 600'. 4th plug filled hole to 40' w/  
heavy mud & dumped 1/2 sbp bulbs in hole & pushed rubber plug to 40' on solid bridge &  
pumped 10 sbp cement through drill pipe filling hole to 0'. Circulated 15 sbp cement  
through drill pipe in rat hole.

Remarks: Halliburton Cementing accomplished the cementing  
w/ 60/40 zogg w/ 2% gell.

I hereby certify that the above plugging instructions were given as herein stated  
and that I ~~(did)~~ (did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1-20-84

INV. NO. 9203 IN

Signed Paul A. Luthis  
(TECHNICIAN)