

RECEIVED
KANSAS CORPORATION COMMISSION

3-8

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

APR 01 1994
4-1-1994
CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-191-22,139-00-00
C NE SW, SECTION 16 TOWNSHIP 34 RANGE 4W

OPERATOR LICENSE # 6785 1980 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR SCHULEIN COMPANY
NAME & 1776 LINCOLN ST #811
ADDRESS DENVER CO 80203

LEASE NAME: KOLARIK #11-16
COUNTY: SUMNER
WELL TOTAL DEPTH: 4545' 147.71

PIPE: 5-1/2" @ 4441'
SURFACE CASING: 8-5/8" @ 309'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: CARL DURR

COMPANY NAME: FIELD OPERATION INC PHONE: _____

WERE: OH 4441'-4545' - SAND BACK TO 4390' & 5 SX CMT - 35 SX @ 850' - 35 SX @ 600' - CIRC 360' TO 0'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 18:00 DAY: 8 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:
PERFS COVERED W/SAND TO 4355' & CAPPED W/5 SX CMT -
5-1/2" RECOVERED 3741' & PULLED TO 877' & 35 SX CMT
SPOTTED - 5-1/2" PULLED TO 601' & 35 SX CMT SPOTTED -
5-1/2" PULLED TO 367' & CMT CIRC TO SURF - REMAINING
PIPE PULLED & CMT TOPPED OFF

REMARKS: ALLIED 60/40 4% GEL

INVOICED
DATE APR 01 1994
INV. NO. 40208
I DID NOT OBSERVE THIS PLUGGING.

1/5
STEVE VAN GIESON (AGENT)