

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21339-00-00
Spot: NENWNW Sec/Twnshp/Rge: 4-10S-19W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: ANDRESON Well #: 1
County: ROOKS Total Vertical Depth: 3730 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3729		200 sx
SURF	8.625	232		165 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: Ordered 370 sx 60/40 pozmix 4% gel cement w/650 # hulls.
DV Tool at 1600' w/400 sx cement

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2015 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3700' and pumped 145 sx cement w/250 # hulls. Pulled tubing to 1900' and pumped 160 sx cement w/400 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/65 sx cement. Visually checked backside and there was cement to surface.

GPS: 39.21906N -099.45310W

Remarks: FEE FUND PROJECT ANDRESON # 1 CONTROL # 20140042-001

Plugged through: TBG

District: 04

Signed: _____

Pat Bedore

(TECHNICIAN)

CM

MAR 11 2015

KCC WICHITA

MAR 30 2015

RECEIVED