

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21943-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 4-10S-19W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: ANDRESON Well #: 4  
County: ROOKS Total Vertical Depth: 4000 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3970		200 sx
SURF	8.625	283		185 sx

Well Type: SWD UIC Docket No: D22049.0 Date/Time to Plug: 03/04/2015 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 1100 # hulls.  
DV Tool at 1600' w/450 sx cement

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2015 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3900' and pumped 200 sx cement w/450 # hulls. Pulled tubing to 2000' and pumped 210 sx cement w/650 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/40 sx cement. Visually checked the backside and it had cement to surface.

GPS: 39.21360N -099.45307W

Remarks: FEE FUND PROJECT ANDRESON # 4 CONTROL # 20140042-003

Plugged through: TBG

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

KCC WICHITA

MAR 30 2015

RECEIVED

Form CP-2/3

~~MAR 09 2015~~

MAR 11 2015

CC:uic