

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-02186-00-00
Spot: SENESE Sec/Twnshp/Rge: 5-16S-14W
1678 feet from S Section Line, 364 feet from E Section Line
Lease Name: NUSS Well #: 2
County: BARTON Total Vertical Depth: 3340 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3439		
SURF	8.625	245		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2015 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement, 1600 # gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1500', 935', 450' and 245'. Ran tubing to 3200' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 500'. Circulated cement to surface with 75 sx cement on surface and casing. Circulated surface pipe to surface with 60 sx cement.


GPS: 38.68582 -098.88523

Remarks: QUALITY WELL SERVICE FEE FUND PROJECT NUSS CONTROL # 20140061-001

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

MAR 30 2015

RECEIVED

MAR 19 2015