

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-02187-00-00
Spot: NENESE Sec/Twnshp/Rge: 5-16S-14W
2289 feet from S Section Line, 306 feet from E Section Line
Lease Name: NUSS Well #: 3
County: BARTON Total Vertical Depth: 3440 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3439		
SURF	8.625	262		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2015 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 1600 # gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

Perforated at 1500', 935', 450' and 260'. Ran tubing to 3200' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 500'. Circulated cement to surface with 80 sx cement on casing. Topped off with 60 sx cement pressured to 400 psi. Topped off surface pipe with 10 sx cement pressured to 500 psi.
GPS: 38.68753 -098.887363

Remarks: QUALITY WELL SERVICE FEE FUND PROJECT NUSS CONTROL # 20140061-002

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

KCC WICHITA
MAR 30 2015
RECEIVED

MAR 19 2015