

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-045-19099-0000
 Spot: SESESE Sec 8 Twp 15 S Rng 21 ☒ E / ☐ W
465 Feet from ☐ N / ☒ S Line of Section
160 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.754550 Long: 95.094090 Date: 2/27/15 12/27/13
 Lease Name: Greg Neis Well #: GNE 01
 County: Douglas Total Vertical Depth: 1150 110 feet

Operator License No: 101 String Size Depth Pulled Comments
 Op Name: STATE OF KANSAS DRIVE - Drive Pipe 9,000 20 0 EST
 Address 1: 266 N. Main St. Ste. 220
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - _____

Well Type: OG - Oil & Gas - (oil) UIC Docket No.: _____ Date/Time to Plug: 1/29/15 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Frank Guilfoyle Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Mike Kepley Witness Type: COMP - Complete 100%

Date/Time Plugging Completed: 1/29/15 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report: Perfs: Top Bottom Thru

Move equipment to location. Run 1" to 100 ft. Wash to 110 ft and hit hard. Pull pipe and had cement in threads. Pull off, need to drill cement out to see if this is oil well converted to water well.
 Move drill rig to location. Run drill steel to 100 ft and start drilling through cement. Drill through about five ft of cement. Wash to 500 ft and pull drill steel out. Move rig. Set up pulling unit. Run 1" to 500 ft, and wash to 900 ft. Crude oil started filling pit. Pull 100 ft of 1" and let sit overnight. Wash back to 900 ft and pump Portland cement to surface. Pull pipe and top off well. Pump total of 297 sacks of cement. Well plugged.

Remarks: Contract number 38595. Control number 20140066-001. NAD 83 by FG. Reg. Sec.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Received
KANSAS CORPORATION COMMISSION

MAR 04 2015

CONSERVATION DIVISION
WICHITA, KS

Frank Guilfoyle
(Technician)

Form: District Plugging Report - _____