

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-15184-00-00
Spot: NENESE Sec/Twnshp/Rge: 18-16S-11W
2299 feet from S Section Line, 343 feet from E Section Line
Lease Name: MARTHA EDWARD Well #: 1
County: BARTON Total Vertical Depth: 3315 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3309		
SURF	10	110		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 2000 # gel and 800 # hulls.
New info on well- 5 1/2" liner to 3150', CIBP at 3146' and 4" welded liner to 3145'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1400', 750' and 110'. Ran tubing to 3100' and pumped 50 sx cement. Pulled tubing to 2250' and pumped 50 sx cement. Pulled tubing to 1400' and pumped 50 sx cement. Pulled tubing to 550'. Circulated cement to surface with 190 sx cement on 4" liner. Pulled tubing. Tied to 4" liner and circulated cement to surface on 7" and 5 1/2" liner with 90 sx cement.
03/18/2015- Cut off all Pipes below ground level and topped off with 40 sx cement.
GPS: 38.65882 -098.57359

Remarks: QUALITY WELL SERVICE FEE FUND PROJECT MARTHA EDWARDS CONTROL # 20140095-001

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

KCC WICHITA

MAR 30 2015

RECEIVED

MAR 19 2015