

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-03035-00-00
Spot: NWNESE Sec/Twnshp/Rge: 18-16S-11W
2304 feet from S Section Line, 993 feet from E Section Line
Lease Name: EDWARDS M Well #: 3
County: BARTON Total Vertical Depth: 3307 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 7 | 3307 | | |
| SURF | 10 | 337 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 2000 # gel and 800 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 750' and 335'. Ran tubing to 3200' and pumped 20 sx gel followed by 100 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 750'. Circulated cement to surface on casing with 140 sx cement. Pulled tubing. Tied to casing and topped off with 45 sx cement pressured to 450 psi. Ran 1" down between surface and casing to 280'. Circulated cement to surface with 120 sx cement.

GPS: 38.65883 -098.57587

Perfs:

Remarks: QUALITY WELL SERVICE FEE FUND PROJECT MARTHA EDWARDS CONTROL # 20140095-002

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

KCC WICHITA

MAR 30 2015

RECEIVED

MAR 19 2015