

To: 1 031152
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-26 253
API NUMBER 15-025-20,883-0000
C SW SE, SEC. 35, T 31 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Operator: Pratt Well Service, Inc.

Name & Address P.O. Box 847

Pratt, KS 67124-0847

660 feet from S section line

1980 feet from E section line

Lease Name Neil Sanders Well # 1

County Clark 171.27

Well Total Depth 5270 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 610

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 4 p.m. Day: 26 Month: 3 Year: 19 91

Plugging proposal received from Ken Gates

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 5270' w/350 sx cement, Perfs at 4440-64, 5112-15, 5132-5140'

1st plug set CIBP at 4400' with 2 sx cement on top,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

and 100 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 26 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4400' and dumped 2 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 450 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 3138' of 5 1/2" casing. MAR 29 1991

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-9-91

Signed Steve Sherout
(TECHNICIAN)

INV. NO. 31426