

11-30-87

To: 1 061036
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,998-6000

SW NW NW, SEC. 36, T 31 S, R 21 W/E

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Wait Well # 1

Operator: Falcon Exploration Inc.

County Clark 169.65

Name & Address 1531 KSB&T Bldg., 125 North Market

Well Total Depth 5220 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 499

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 2 a.m. Day: 30 Month: 11 Year: 19 87

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1120-29'

1st plug at 1130' with 50 sx cement, 2nd plug at 530' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 a.m. Day: 30 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1130' with 50 sx cement,

2nd plug at 530' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

DEC 2 1987

Conservation Division Wichita, Kansas

12-2-1987

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)

INVOICED

Signed Paul A. Luthi (TECHNICIAN)

DATE 12-4-87

INV. NO. 19098

CORRECTED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... *November 20, 1987* month day year

API Number 15- 025-20,998-0000

OPERATOR: License # 5316 Name Falcon Exploration Inc. Address 1531 KSB&T Bldg, - 125 N. Market City/State/Zip Wichita, Kansas 67202 Contact Person Micheal S. Mitchell Phone 316-262-1378

SW.. NW.. NW.. Sec. 36.. Twp. 31.. S, Rg. 21.. XX East XX West *4290* Ft. from South Line of Section *4950* Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5380 Name Eagle Drilling Inc. City/State Wichita, Kansas, 67277

Nearest lease or unit boundary line *330* feet County Clark

Well Drilled For: Well Class: Type Equipment: XX Oil Storage Infield XX Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Wait Well # 1 Ground surface elevation feet MSL

Domestic well within 330 feet: yes XX no Municipal well within one mile: yes XX no

Depth to bottom of fresh water 100' Depth to bottom of usable water 200'

Surface pipe by Alternate: 1 2 Surface pipe planned to be set 225'

Conductor pipe required 0 Projected Total Depth 5350' feet

Formation Mississippian

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications. Date 11-18-87 Signature of Operator or Agent Micheal S. Mitchell Title President

For KCC Use: Conductor Pipe Required feet Minimum Surface Pipe Required 200 feet per Alt (1) X

This Authorization Expires 5-17-88 Approved By P.A. J.F. 11-7-87 * WAS : 2310' FSL Lease Line 330' 11-25-87

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

AS ORIGINALLY FILED

1st plug @ ft. deep or formation with feet of. 2nd plug @ ft. deep or formation with feet of. 3rd plug @ ft. deep or formation with feet of. 4th plug @ ft. deep or formation with feet of. 5th plug @ ft. deep or formation with feet of. (2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

Handwritten log: PUSHER Rutch Steiner TD 5320 FORMATION MISS SURFACE PIPE 8 5/8 @ 499 ANHYDRITE 1120 ELEVATION STARTING TIME & DATE 9:00 AM 11-30-87 COMPLETION TIME & DATE 5:30 AM 11-30-87 1st PLUG @ 1130 FT. W/ 50 SX 2nd PLUG @ 530 FT. W/ 50 SX 3rd PLUG @ 400 FT. W/ 10 SX 4th PLUG @ 1 FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Hall 60/40 2/6/87 P.A. S. TECHNICIAN No one saw

RECEIVED STATE CORPORATION COMMISSION DEC 2 1987 CONSERVATION DIVISION Wichita, Kansas