

To: 1 051585
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-033-10028-0000
12/61
106R
API NUMBER 15-
App. C N/2, SEC. 14, T. 31 S, R 16 W/E
3960 feet from S section line
2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5238
Operator: Petroleum, Inc.
Name &
Address 301 N. Main, Ste. 900
Wichita, KS 67202

Lease Name Hashknife "B" Well # 1
County Comanche 159.97
Well Total Depth 4922 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 540

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____
Address P.O. Box 632, Greensburg, KS 67054-0632

Company to plug at: Hour: 10 a.m. Day: 16 Month: 10 Year: 19 92

Plugging proposal received from Terry Naylor
(company name) Petroleum, Inc. (phone) 316-783-8471

were: 4 1/2" at 4920' with 100 sx cement, PBTD 4913', Perfs at 4894-98, 4904-08'
1st plug sand back to 4560' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 16 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4560' and dumped 4 sx cement on top of sand
through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2450' of 4 1/2" casing. OCT 22 1992
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-29-92
WV. NO. 36631

Conservation Division
Wichita, Kansas
Signed Richard W. Lacey
(TECHNICIAN)