

10-25

To: 1 040476
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,666-00-00
C NE SE, SEC. 26, T 31 S, R 16 W/EX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Operator: American Warrior, Inc.
Name & Address: P.O. Box 399
Garden City, KS 67846

Lease Name Shuette Well # 7
County Comanche 163.47
Well Total Depth 5030 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 25 Month: 10 Year: 19 90

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 5029' w/170 sx cement, PBD 4853', Top perfs at 4792-97'
1st plug sand back to 4740' with 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx
cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 25 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, and 125 sx cement.
Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-5-90
INV. NO. 29818

RECEIVED
OCT 30 1990
10-30-1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Stephen J. Pfeifer
(TECHNICIAN)