

7-5

2-100596

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

STATE CORPORATION COMMISSION

JUL 17 1990

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER: 15-173-20.668-6000

C W/2 NW NW, SECTION 8 TOWNSHIP 28 RANGE 1W

OPERATOR LICENSE # 5822 FEET FROM S SECTION LINE _____
FEET FROM E SECTION LINE _____

OPERATOR Gressel Corporation
NAME & Box 322
ADDRESS Haysville, KS 67060

LEASE NAME: Dugan #1-8
COUNTY: Sedgwick
WELL TOTAL DEPTH: 3690 PBTB 3404'
CONDUCTOR PIPE: 4-1/2" @ 3419'/125 ex
SURFACE CASING: 8-5/8" @ 342'/225 ex

119.93

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: Perf 3350-3356' - 4 shot

PLUGGING CONTRACTOR: Gressel Corporation
ADDRESS: Box 322, Haysville, KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: 4:00p DAY: 5 MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Curt Ledbetter
COMPANY NAME: Gressel Corporation PHONE: 316-522-1560

WERE: Sand 50' above top perf & dump 6 ex cmt - shoot & pull pipe - cmt from 400' to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { X } PART { _____ } NONE { _____ }

COMPLETED: HOUR: 5:00p DAY: 5 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Pump 35 ex cmt down 4-1/2" on bottom to 3400' & top of cmt - tagged at 3300' - shot & pulled 2300' of 4-1/2" 1250' - spotted 25 ex cmt & 1 ex hulls - displaced 15 bbls water - pulled 4-1/2" to 400' - circulated to surface with 125 ex cmt - pulled pipe out - topped off.

REMARKS: Allied #6959 60/40 4% gel

I DID OBSERVE THIS PLUGGING.

John Sanders
John Sanders (AGENT)

INVOICED
DATE 7-24-90
INV. NO. 28713

FORM CP-2/3
REV. 3/90