

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1971  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 200 W. Douglas Wichita, Ks

Lease Name Chitwood Unit Well No. D-8

Location NE/NW/NW Sec. 26-28-128 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4415

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:00 AM Day 18 Month 2 Year 1971

The above well was plugged as follows:

350 ft of 10 3/4 surface pipe cemented with 250 sacks. 4398 ft of

5 1/2 long string cemented with 400 sacks. Top perf. 4320 ft. Sand

back to 4300 ft, 5 sacks cement with bailer. Pulled 1700 ft of 5 1/2.

Set 20 ft rock bridge at 340 ft, 40 sacks cement. Mud to 40 ft,

15 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/19/71INV. NO. 3368-WSigned Y. Russell Blevins  
Well Plugging Supervisor