

10 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

01481

15-007-~~00003~~-00-00

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 21 1962

CONSERVATION DIVISION  
WICHITA, KANSAS

9-21-1962

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Champlin Oil Refining Company

Complete Address: 303 Koch Bldg., Wichita, Kansas

Lease Name #2 Davis Ranch "J" Well No. #2

Location 5' N of W/2 SW NE Sec. 12 Twp. 34 Rge. 15 (E) (W) X

County Barber Total Depth 4867'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: H-30 Drilling Inc.

Address: 709 Petroleum Bldg., Wichita Kansas License No.     

Operation Completed: Hour 4: PM Day 16 Month Sept Year 1962

The Above well was plugged as follows:

850' of 8 5/8" set. Hole filled to 840' with heavy drilling mud, 1/2 sack hulls, 1st cementing plug, (30 sacks cement) by Halliburton. 600' of 8 5/8" pulled. 200' of <sup>13 3/8</sup> surface pipe circulated with cement. Hole filled to 180' with heavy drilling mud, 1/2 sack hulls, 2nd cementing plug and 25 sacks cement. Hole filled to 30' with heavy drilling mud, 1/2 sack hulls, 3rd cementing plug, 25 sacks of cement to base of cellar. Rat hole bridged and 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 9/21/62

INV. NO. 5436-W

Signed: Hermon Justus  
Well Plugging Supervisor