

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED FORM CP-1
STATE CORPORATION COMMISSION
Rev. 2/89

DEC 16 1991

WELL PLUGGING APPLICATION FORM
(File One Copy)

Conservation Division
Wichita, Kansas

API NUMBER 15-025-21,057-000 (of this well).

12-16-1991

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003 6-92

ADDRESS 110 South Main/ Suite 500/ Wichita, Ks 67202 PHONE # (316) 265-9697

LEASE (FARM) Harden "A" WELL NO. #1-34 WELL LOCATION SE NW SE COUNTY Clark

SEC. 34 TWP. 31S RGE. 21W or TOTAL DEPTH LTD 5296' PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 676' CEMENTED WITH 150 60/40 Poz SACKS

CASING SIZE 4-1/2" SET AT 5294' CEMENTED WITH 175 Thix-Set SACKS

PERFORATED AT Morrow Sand from 5141-5144' and from 5160-5164' (4 spf)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Set CIBP @ +/-5100' and cap with 4 sacks of cement. Shoot

& pull casing. Pump the following down 8-5/8" surface casing: 300# hulls, 10 sacks of gel,

50 sacks of cement, 10 sacks of gel, 100# hulls, 8-5/8" wiper plug & 150 sacks of cement.

(60/40 Pozmix 6% Gel) (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-6-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 532-5292

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Shawnee Well Service LICENSE NO. 30346 3-92

ADDRESS 127 E. B., Attica, KS PHONE # (316) 254-7893

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: 12-12-91

(1)

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

December 16, 1991

McCoy Petroleum Corp
110 S Main Ste 500
Wichita KS 67202

Harden A 1-34
API 15-025-21, 057-6600
SE NW SE
Sec. 34-31-21W
Clark County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238