


12-9-64

WELL PLUGGING RECORD

15-007-00663-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 18 Twp. 31S Rge. 13W (#) (W)
Location as "NE/CNW/SW" or footage from lines SW NE NW
Lease Owner A. G. Hill, Oil Producer
Lease Name Truelove Well No. 1
Office Address 2717 1st Nat'l. Bldg., Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-6-64 19__
Application for plugging filed 12-6-64 19__
Application for plugging approved 12-6-64 19__
Plugging commenced 12-6-64 19__
Plugging completed 12-6-64 19__
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | | | |
| | | | | 8 5/8" | 238' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud to 235' Plug 1/2 sk. hulls 25 sks. cement
Filled hole w/mud to 40' Plug 1/2 sk. hulls 10 sks. cement
2 sks. cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 64

My commission expires April 1, 1967

Ulauda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: A. G. Hill, Oil Producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: TRUELOVE #1
 LOCATION: SW NE NW Sec. 18-31S-13W
 BARBER COUNTY, KANSAS
 COMMENCED: 11-24-64
 COMPLETED: 12-6-64

15-007-00063-0000

| | | |
|------|-------------|---|
| 0 | 210 | Redbed |
| 210 | 1125 | Redbed & Shale |
| 1125 | 1665 | Shale & Lime |
| 1665 | 2020 | Lime & Shale |
| 2020 | 2270 | Lime |
| 2270 | 2555 | Lime & Shale |
| 2555 | 2920 | Shale & Lime |
| 2920 | 2975 | Lime |
| 2975 | 3382 | Shale & Lime |
| 3382 | 3740 | Lime & Shale |
| 3740 | 3785 | Sand & Shale |
| 3785 | 3800 | Lime & Shale |
| 3800 | 4322 | Lime |
| 4322 | 4385 | Lime & Shale |
| 4385 | 4400 | Lime & Chert |
| 4400 | 4410 | Lime |
| | <u>4410</u> | <u>Rotary Total Depth - D. & A.</u> |

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 9 1964
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 238' with 175 sacks HA5 Posmix

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Truelove #1 well, located SW NE NW of Section 18, Township 31 South, Range 13 West, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 8th day of December, 1964.

Ulanda Nichols

 Ulanda Nichols

My Commission Expires April 1, 1967