

JAN 25 1983

1-25-83

CONSERVATION DIVISION
Wichita Kansas

15-607-21167-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 18 TWP 31S RGE. 13 N/W
Location as in quarters or footage from lines:

Locate Well
correctly on above
Section Platt.

Lease Owner Eagle Explorations, Inc.
Lease Name Smith Well No. 1
Office Address 107 North Market Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Oil and gas
Date Well Completed 8-29-81 to 11-3-82
Application for plugging filed 1-14-83
Plugging commenced 1-18-83
Plugging completed 1-20-83
Reason for abandonment of well or producing formation
Not economical to produce
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. McArtor
Producing formation Mississippian Depth to top 4290 bottom 4298 T.D. 4650
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface pipe		0		8 5/8		
4 1/2" casing		0	4650	4 1/2		3560'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

CIBP at 4360', setting over the Simpson sand formation. Sand plug back from 4360-4240 with 13 sacks sand, shot pipe off at 3560'.
3 sacks hulls, 25 sacks gel, 70 sacks cement--50/50 poz mix 4% gel, 3% CC
20 sacks gel, 1 hull, 8 5/8 wiping plug, 100 sacks cement (50/50 poz mix 4% gel, 3% CC)
plugging time 11:15 AM.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc. Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Baird (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Judy Baird
Box 847 Pratt, Kansas 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January 19 83

Charlene M. Dudley
Notary Public.

My Commission expires: 9/10/86

