

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

3-20-92

API NUMBER 15-025-21,057-0000

LEASE NAME Harden "A"

WELL NUMBER 1-34

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 34 TWP. 31S RGE. 21 (or (H))

COUNTY Clark

Date Well Completed 2-16-91

Plugging Commenced 12-6-91

Plugging Completed 12-6-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR 5003

ADDRESS McCoy Petroleum Corporation

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-5-91 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Sand Depth to Top _____ Bottom _____ T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	676	8-5/8"		None
		0	5294	4-1/2"		4425

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ +5100' and cap with 4 sacks of cement. Shoot @ 4425'. Pull 4425' of casing.

Pump the following down 8-5/8" surface casing: 300# hulls, 10 sacks of gel, 50 sacks of cement, 10 sacks of gel, 50 sacks cement, 10 sacks of gel, 100# hulls, 8-5/8" wiper plug & 150 sacks cement. (60/40 Pozmix 6% gel.)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address 127 E. B, Attica, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *[Signature]*

(Address) 110 S. Main, Suite 500
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 20 day of December, 19 91

[Signature]
Notary Public



1-8-92