

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

4-3-91

15-025-20883-00-00

API NUMBER 15-025-21,883-1000

LEASE NAME NEIL SANDERS

WELL NUMBER 1

 Ft. from S Section Line
 C SW SE
 Ft. from E Section Line.

SEC. 35 TWP. 31 RGE. 21 (X or W)

COUNTY CLARK

Date Well Completed

Plugging Commenced 3-6-91

Plugging Completed 3-26-91

LEASE OPERATOR PRATT WELL SERVICE, INC.

ADDRESS P O BOX 847 PRATT, KANSAS 67124

PHONE#(316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on MARCH 5, 1991 (date)

by STEVE DURANT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 5270

Show depth and thickness of all water, oil and gas formations.
 PERFS: 4440-64; 5112-15; 5132-40.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	610	8 5/8	610	0
		0	5270	5 1/2	5270	3140.35' 78 1/2 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

3-6-91: RIG UP UNIT, DIA LOG SET BRIDGE PLUG DUMPED 2' SX CEMENT ON TOP OF PLUG CUT OFF AT FREE POINT AND PULLED 78 1/2 JTS. OF CASING.

3-26-91: HALLIBURTON TOP HOLE PLUGGED WITH 3003 hulls, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8 PLUG, 100 SX CEMENT, 6% AND 60-40 POZ MAX PRESSURE 400# ISIP 300#.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. %*(#

Address P O BOX 847 PRATT, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

(Employee of PLUGGING CONTRACTOR)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO Box, Inc.



RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1991

APR 03 1991

My Commission Expires Feb. 6, 1993

Notary Public