

2-12-81

15-025-20403 0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Clark County, Sec. 36 Twp. 31S Rge. 21 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
330' FEL & 330' FNL

Lease Owner Reading & Bates Petroleum Company
Lease Name Melia Well No. 1
Office Address 1100 Mid Cont. Bldg., 409 S. Boston
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 1/9 1981
Application for plugging filed 1/16 1981
Application for plugging approved 19
Plugging commenced 1/9 1981
Plugging completed 1/9 1981

Reason for abandonment of well or producing formation
Dry Hole


If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5350'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement plug set from 782' to 662' with 60 sks Class "H".

Cement plug set from 40' to surface with 20 sacks Class "H".

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B.J. Hughes

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Reading & Bates Petroleum Company (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1100 Mid Cont. Bldg. 409 S. Boston
(Address) Tulsa, Ok 74103

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19

Notary Public.

My commission expires _____

STATE PLUGGING COMMISSION
FEB 12 1981
CONSERVATION DIVISION
Wichita, Kansas

Reading & Bates Oil & Gas
MELIA #1

Contractor: RINE DRILLING

Started: December 30, 1980

C NE NE NE
36 31S 21W
Clark County, Kansas

15-025-20405-0000

Completed: January 10, 1981

LOG

Surface 0 - 76'
Redbed 76 - 1590'

Ran 37 jts. 9 5/8" csg., set @
1461', cmt. w/ 350 sx poz, 2% c.c.
1/4# Flo., 6% gel + 150 sx H, 2% c.c.
TOTCO - 1/2 @ 293, 1/2 @ 760'.

Redbed & Anhydrite 1590 - 2300'
Anhydrite & Shale 2300 - 2410'
Dolomite 2410 - 2660'
Dolomite & Shale 2660 - 2855'
Lime & Shale 2855 - 5350'

TOTCO - 1 1/2 @ 2300'

Plugged + abandoned thru open end
D.P. as follows:

60 sx cmt. @ 782'
5 sx in RH
5 sx in MH

Ks State Plugger:
Clarence Thompson
Garden City, Kansas

STATE OF KANSAS:)
) ss:
SEDGWICK COUNTY:)

I, E.J. Rine, do hereby certify that the above is a true and accurate log of the
MELIA #1, located C NE NE NE 36 31S 21W, Clark County, Kansas.



E.J. Rine, President

Subscribed and sworn to before me this 14th
day of January, 1981.


Marsha J. Hughes, Notary Public

My appointment expires: 6-20-84

STATE RECEIVED
FEB 12 1981
CONSERVATION DIVISION
Wichita, Kansas



COPY