

10-21-92

15-033-10628-0005  
December, 1961

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

No. 04-2-111

API NUMBER \_\_\_\_\_  
LEASE NAME Hashknife "B"  
WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3980 Ft. from S Section Line  
2620 Ft. from E Section Line

LEASE OPERATOR Petroleum, Inc.  
ADDRESS 301 N. Main - Suite 900, Wichita, KS 67202  
PHONE (316) 291-8200 OPERATORS LICENSE NO. 5238

SEC. 14 TWP. 31S RGE. 16 (E or W)  
COUNTY Comanche

Character of Well Gas  
(Oil, Gas, O&A, SMD, Input, Water Supply Well)

Date Well Completed Jan. 1962  
Plugging Commenced 10-9-92  
Plugging Completed 10-16-92

The plugging proposal was approved on October 16, 1992 (date)  
by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? submitted with Form CP-1

Producing Formation Mississippi Depth to Top 4838 Bottom 4922 T.D. 4922

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	540'	None
				4 1/2"	4920'	2450'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Set sand plug to 4565'. Cutoff 4 1/2" csg. and pulled 2450'. Pumped 300# hullts, 10 sx: gel, 50 sx: cement, 10 sx: gel, 100# hullts, 8 5/8" rubber plug, 150 sx: cement, MP 600#, S.I. press. 50#.

Name of Plugging Contractor Allied Cementing Co. License No. \_\_\_\_\_  
Address P. O. Box 628, Great Bend, KS 67530-0628 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROLEUM, INC.  
STATE OF Kansas COUNTY OF Sedgwick, ss.

Paul Kreutzer (Employee of Operator) or Wichita, Kansas (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Paul Kreutzer  
(Address) 301 N. Main - Suite 900, Wichita, KS 67202



SWORN TO before me this 20 day of October, 19 92  
Sherry Fraser  
Notary Public

My Commission Expires: 3-20-94

USE ONLY ONE SIDE OF EACH FORM

