

9-1-83

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-033-20596-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Comanche SEC. 25 TWP. 31S RGE. 16E
Location as in quarters or footage from lines:
NE-SW-NE

Locate Well
correctly on above
Section Platt.

Lease Owner Canady Oil Inc.
Lease Name Schuette Well No. 1
Office Address 710 Petroleum Building Wichita, Kan
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 7-83
Application for plugging filed 7-13-83
Plugging commenced 7-14-83
Plugging completed 7-18-83
Reason for abandonment of well or producing formation

Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Durante

Producing formation Mississippi Depth to top _____ bottom T.D. 4,997

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	0	0	348	8 1/2"		
		348	4997	4 1/2"		350 Ft.

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Plug Bottom Dump 1 sack cement on Bridge
plug. Set plug at 4,870 Ft. Dump 5 sacks cement. Top Plug. Set plug
at 350 Ft. Called Haliburton pump 200 sacks cement 2% Gel & 3% Chloride.
3 sacks hulls in front of cement. Mix 20 sacks cement to fill hole back up.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chet Shephard Drilling Co.

STATE OF Kansas COUNTY OF Cowley, ss.


(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts and matters herein contained and the log of the above-described well as
stated are true and correct. So help me God.

(Signature) Chet Shephard
Box 9 Genda Springs, Kan.
(Address)

SFP 1983

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this day of AUG 30 1983, 19



Zoe Doolittle
Notary Public.

My Commission expires: