


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Comanche County, Sec. 25 Twp. 31 Rge. 16 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CNW $\frac{1}{4}$
Lease Owner Barbara Oil Company
Lease Name E. Schmette Well No. 1
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed 9-5-53 19
Application for plugging filed 9-5-53 19
Application for plugging approved 9-5-53 verbally 19
Plugging commenced 9-6-53 19
Plugging completed 9-6-53 19
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5000' to 500' with 9.6% mud. Plug at 500' with 25 sacks cement. Mud to 20' below bottom of cellar, cement to base of cellar.

(Well log will be forthcoming at a later date).

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. C. Patton Company
Address 613 Orpheum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. F. Ramsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. F. Ramsey*
Landman
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of September, 1953.

My commission expires March 2, 1957

W. J. Tucker
Notary Public.

23-8390-5 6-51-20M
PLUGGING
FILE SEC 25 T 31 R 16 W
BOOK PAGE 127 LINE 82

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1953
CONSERVATION DIVISION
Wichita, Kansas

Barbara Oil Company
 E. C. Schuette Well #1
 Total Depth
 Comm.
 Comp.
 Contractor R. C. Patton Co.,

Located Ctr. NW/4, Section 25, T31S, R16W
 Comanche County, Kansas.

5000 Ft CASING RECORD.
 8/15/53 10 3/4" Casing at 523 Ft.
 9/6/53 Cemented with 325 Sacks Cement.

15-633-1000-0000

Soil & Sand	160
Red Bed	260
Red Bed, Gyp & Shells	310
Red Bed	557
Red Rock, Shells & Sand	1225
Red Bed & Salt	1705
Shale & Shells	2020
Shale, Shells & Lime	2130
Shale & Shells	2200
Shale & Anhydrite	2290
Shale & Lime	2865
Shale	3245
Shale & Lime	3752
Lime	3950
Shale & Lime	4120
Lime	4310
Shale & Lime	4390
Lime K.C.	4443
Lime	4595
Shale & Lime	4668
Lime	4760
Shale & Lime	4928
Lime	4952
Lime Miss	4980
Shale	5000
Total Depth	5000

STATE OF Kansas COUNTY OF Sedgewick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By R. C. Patton

Subscribed and sworn to before me this 14th day of September 1953.

W. O. Kendrick
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

My Commission Expires Oct. 4th 1956.

SEP 16 1953
 CONSERVATION DIVISION
 Wichita, Kansas