

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Docket Number D 9512
API NUMBER 5/31/62

15-033-10021-0000

3-18-92

LEASE NAME Nielsen Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

3960' Ft. from S Section Line

1320' Ft. from E Section Line

LEASE OPERATOR American Warrior Inc.

SEC. 1 TWP. 31 RGE. 17 (W)

ADDRESS Box 399; Garden City, Kansas 67846

COUNTY Comanche

PHONE#(316) 275-9231 OPERATORS LICENSE NO. 4058

Date Well Completed 5/31/62

Character of Well Dual completion - Gas & SWD

Plugging Commenced 7/10/91 2:00 p.m.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/12/91 10:00 a.m.

The plugging proposal was approved on 7/9/91 (date)

by Steve Durant- District 1 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Mississippi Depth to Top 4870' Bottom 4993' T.D. 5030'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi Per	Perf. 4879-4908'	0	5025	2 7/8	5025	320 none
Council Grove	Perf's 2543-3324'	0	3391	2 7/8	3391	320
		0	446	8 5/8	446	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 20 sks. 65/35 pozmix; 6% gel at 4412'. Well went on vacumm. No fill-up.
Mixed 40 sks. 65/35 pozmix; 6% gel. Top of cement at 3152'. On 7/12/91 hook up to disposal string. mix 100 sks. 65/35 pozmix, 6% gel. Maximum pressure 250 - shut in 150. Hook up to gas string mix 15 sks. Closed in 150#. Mix 10 sks. to fill disposal string.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address Pratt, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1992

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior Inc.

STATE OF Kansas COUNTY OF Ness, ss.

Dean Ives (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Ives

(Address) 1209 Haney, Hays, KS 67601

CONNIE J. BASE
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 5-5-94

DESCRIBED AND SWORN TO before me this 16th day of March, 19 92

Connie J. Base
Notary Public

My Commission Expires: 5-5-94