


9-30-54

15-057-10064-00-01

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 7 Twp. 31 Rge. 13 (E) (W)
Location as "NE/CNW%SW%" or footage from lines C SW SE
Lease Owner National Cooperative Refinery Association
Lease Name Gant "A" Well No. 2 (SWD#1)
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal Well.
Date well completed September 23, 1954
Application for plugging filed July 26, 1954
Application for plugging approved July 27, 1954
Plugging commenced September 22, 1954
Plugging completed September 23, 1954
Reason for abandonment of well or producing formation Plugging of producing wells which utilized this disposal well.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4651 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN.	PULLED OUT
				13 3/8"	231'	None
				7"	4557'	None
				5 1/2" Liner, 165' Long, with top at 4485'		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud, tubing, and casing to 300'. Mixed 50 sacks cement plus 25 cubic feet of Strata-Crete plus 6 sacks of Cal-Seal, pumped down casing, filled up to 250'. Cemented with 150 foot Pozmix cement up to base of cellar by Halliburton Cementing Company.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Cooperative Refinery Association
Address 305 Rule Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 54

My commission expires June 30, 1958.

C. Orville May
C. Orville May Notary Public.

PLUGGING
FILE SEC 7 T 31 R 13u
DATE FILED 9/26

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION

WELL LOG

COMPANY: National Cooperative Refinery Ass'n.
FARM: Gant "A" 2
T. D. 4761'
COMM: 8-19-47 Comp: 9-5-47

Sec. 7, Twn. 31, Rge. 13W
SWC SE $\frac{1}{4}$
Barber County

15-087-10024-00-01

Lime 4579'
Sand & Shale 4587'
Hard Sand & Shale 4593'
Shale 4622'
Lime 4629'
Lime & Shale 4651'
Lime & Chert. 4666'
Lime 4742'
Cherty Lime 4755'
Lime 4761'

Completed as a Salt Water *Disposal well*

PLUGGING
FILE SEC 2 T 31 R 13W
BOOK PAGE 51 LINE 26

RECEIVED
A. R. C. M.
ATWINDW
FEB 10 1947

RECEIVED
STATE COM
JUL 1947
CONSERVATION